First Solar – Switch Station Technical Review

Ryan Zwilling & Paul F. Legac; May 25, 2017

Summary

The Switch Station projects (Switch Station 1 & Switch Station 2, collectively the "Projects") consist of approximately 236 MW_{DC} of photovoltaic (PV) generation near the Moapa River Indian Reservation approximately 40 miles northeast of Las Vegas, NV and within 30 miles of JPM's River Mountains solar project. The Projects cover approximately 1,700 acres of public land administered by the United States Bureau of Land Management (BLM). The Projects were developed and are being brought to commercial operations by First Solar. The general characteristics of each project are outlined in the table below. Both projects use First Solar Series 4 Version 3 (S4v3) modules mounted on First Solar single-axis trackers. The Point of Interconnection (POI) is NV Energy's existing 230 kV Harry Allen substation located less than 1 mile to the southwest of the projects. All of Switch 1's power is to be sold under a 20 year PPA with Nevada Power Company (NPC) and Switch 2's power will be sold under two separate 20 year PPAs with NPC (35%) and Sierra Pacific Power Corporation (65%).

Project	MW _{DC} ¹	MW _{AC} ¹	Location	Module Mfgr.	inverter Mfgr.	Mounting System	Expected COD
Switch Station 1 (Switch 1)	137.53	104.65 (limited to 100 MW at POI)	40 miles northeast of	First Solar Series 4 (FS4-117A-3 to	GE LV5-1540 (4 MVA each); 27 @ Switch 1	First Solar single-axis	7/2017
Switch Station 2 (Switch 2)	98.26	81.69 (limited to 79 MW at POI)	Las Vegas, NV	FS4-120A-3)	21 @ Switch 2	trackers	10/2017

Note 1: DC capacity is relevant for purposes of the understanding the plant's physical size and for O&M cost benchmarking. AC capacity is relevant for discussion related to inverters and all grid-facing plant aspects (e.g. substation, PPA, interconnection agreement).

Key Concerns (both Projects unless specified otherwise):

- Modules: First Solar Series 4 Version 3 (S4v3) modules are new to our portfolio and thin film (Cadmium Telluride, CdTe, here) modules are a relatively small portion of the JPM portfolio. We have similar modules (S4v2) and trackers at the sPower 2 transaction's Redwood Cluster (73 MW_{DC}, COD in late 2015). They operate on the same physical principles as the more common crystalline silicon panels but have different components and manufacturing processes. Series 4 modules have higher breakage rates than crystalline silicon due to their frameless design. We do not see the modules as presenting any undue risk to the Projects (See: "Module Technology" in the technical appendix).
- Module QA/QC and testing: No project-specific module testing or third party factory audits have occurred to date.
 First Solar (which arguably has a best-in-class internal quality program, a view held by Leidos as well as other industry participants we have spoken to including third party factory inspector CEA) uses an ongoing program to monitor product reliability for known or perceived risks. It includes weekly sampling and ongoing quarterly reliability tests, including short term performance tests and long-term environmental exposure tests across all production lines.
 - To date, Leidos has received 33 weeks' worth of reliability covering 85% of the module production for Switch 1, and has confirmed that such results are acceptable. We will require the rest of the testing information with respect to Switch 1 and 2 modules prior to funding.
 - The latest results available from VDE, a reputable third party lab, are from Q1 2016 modules and are indicated to be passing, although little detail was provided. We have reviewed the Leidos analysis and limited third party test reports and consider the available information to be acceptable for Switch 1 modules, although some clarifications and updates (as results become available) are needed to close this out prior to Substantial Completion funding.
- Over-generation Curtailment: Economic curtailment is not allowed under the PPAs and Switch 1 & 2 will be
 network resources, the highest transmission priority. As is typical, reliability or emergency curtailment is not
 reimbursed under the PPAs. As a part of its transmission study, Leidos has assessed the risk of over-generation
 curtailment, where production exceeds load on a regional level and may be invoked and categorized as non
 reimbursable reliability-driven curtailment. We have accepted Leidos' baseline forecast of 0.4% initially ramping to
 1.4% in 2021.

Our review is based on various project documents, all of which are currently draft version, a Leidos Independent Engineer's Report, (319871 Switch Station IER D4 dated 11May2017) and a draft Leidos Transmission Assessment (Draft 3 dated

11May2017). A JPM site visit was also conducted on 18 April 2017 and informs this report. A second site visit is planned closer to mechanical completion of Switch 2.

A table summarizing key review areas and major findings is shown below, with significant issues discussed following the table. Maps, figures and year by year production values for each project follow the discussions. A detailed review is attached as an appendix for additional details and reference.

	Switch Station 1	Switch Station 2
	Solar Resource	
JPM Haircuts: Long-term &	Long term: 1.5%; (recent solar projects have i	anged from 0-2.5% long-term). We may
10-yr average	increase our haircut if First Solar's performa	nce testing plan is not satisfactory.
7	288.5 GWh/yr.; (10-yr average after JPM	210.1 GWh/yr.; (10-yr average after JPM
Annual Output projection	adjustments & curtailment)	adjustments & curtailment)
Attitude of a part of a second	see Table 1a & 1b for year by year values	see Table 2a & 2b for year by year values
JPM Capacity Factor	32.9%	30.3%
On-site Period of Record	No onsite measurements; relied on satellite t	pased sources. This is unusual for a project o
(POR)	this size and we have accounted for this in ou	r haircut. See technical discussion below
Long term reference(s)	Satellite-derived irradiance data from Clean F	
Long term irradiance	to the O FOX hadron to the investor	Control discussion below
(kWh/m²)	2,079; we applied a 0.5% haircut to this value	
	Undeveloped desert with dry stream beds (a	ka "washes"); site generally slopes from
Terrain and Ground cover	higher elevations in the west to lower elevati	ons in the east.
Séadula Daguadation	First Solar states 0.5%/year which we did not	accept; recommend using 0.75%/year
Module Degradation	degradation for the JPM booking case as we'	ve done historically.
Inverter Considerations	We believe a lower 1 st year availability of 97.	5% is warranted; adopted our standard
Inverter Considerations	98.5% long-term availability starting year 2. (Leidos recommended 99% for years 2+.)
AC Clipping Adjustment	See technical discussion below.	
Other considerations	Leidos did brief checks of manufacturer inpu	
Curtailment	Based on Leidos congestion analysis; expecta	tion of 1.4% by 2021. See discussion above
	We did not accept Leidos value of 3.7% as it	s well below what we have seen projected l
Uncertainty (10 year)	other IEs; used 5.2% to align with accepted v	alues by other IEs for this region.
	There is the potential for an additional 21 M	
Buildout	project POI. We are working to ensure appro	priate build-out protections (mainly with
	respect to electrical losses) are in place.	
	Modules	
	1,158,600 S4v3 modules (types FS-117 &	822,240 S4v3 modules (types FS-117 & FS
Models and features	FS-120); See discussion above.	120); See discussion above.
1014 F	Favorable to date (sPower Redwood cluster	nave similar), but somewhat limited data
JPM Experience	available. 0.18% first year breakage/replacer	
	In production since 2014; S4v2 produced in 2	2015; current S4v3 technology (with mostly
Track record	minor process changes vs. S4v2) has been in	
	of 6,256 MW _{DC} through 2016. We are seekin	g to reconcile these figures vs. sPower 2
	experience and to make sure the O&M budg	et and spare parts are sufficient.
	Due to frameless glass-on-glass design, breal	kage rates (0.08% overall) are higher than fo
Key considerations	crystalline silicon PV - accounted for in O&M	and stress cases. First Solar has extensive
•	deployment in similar hot/dry climates.	
Warranties	Standard 10 yr workmanship. Performance:	98% in year 1, then 0.5%/year to year 25
	Module QA/QC and Testing	
Bankability Study	Leidos (standalone report not provided, but	good detail provided within IE report)
Qualification Testing of	None provided by First Solar, checked by Lei	

	Switch Station 1	Switch Station 2
Accelerated Life Testing of Bill-of-Materials & Mfg. Process	First Solar uses an ongoing program to monit risks. See discussion above.	cor product reliability for known or perceived
In-Plant Inspection of	Several dozen in-process visual, electrical, or	mechanical QA/QC steps. Leidos and others
Process - Sponsor	in the industry have a favorable view.	
In-Plant Inspection of	None. We have accepted First Solar's own pr	ocess QA/QC and ongoing reliability test
Panels - 3rd party	data, as we also did for sPower 2.	
	Racking/Trackers	
Models and features	First Solar single-axis tracker; rows individual	ly driven similar to NEXTracker NX Horizon.
IDM Eventiones		cluster, understood to be working acceptably
JPM Experience	after year 1 teething issues were addressed.	, ,
Warranty	Working to confirm the details post First Sola	ar Electric (FSE) warranty
	We have recently learned that First Solar has	
Ohan I.	Leidos, the tracker design is very simple, i.e.	
Obsolescence		act obsolescence strategy and, if needed, will
	ensure appropriate protections are in place.	
	Inverters	
Models and features	48 total GE LV5-1540 (4 MVA) supplied by GE	
	NextEra's Longleaf and Indigo Plains portfolio	
JPM Experience	a mix of 1 MVA and 4 MVA inverters. See dis	
	Deployed since late 2015, GE Power reported	
Track record	inverters worldwide with over 3,100 MW _{AC} o	
	(not including these projects) have 1,217 MV	
Warranties	5.5 year warranty from delivery	
	EPC	
Major contractors	First Solar Electric (FSE) full turnkey EPC; Con	tracts to be executed prior to funding
Experience		ts in North America through the end of 2016.
Electrical	Standard substation with two 230 kV, 110 M	
	Generally standard; Seeking further document	
Completion Procedures:	grid connection and that all necessary tasks	have been completed to a torquoing pile
Mechanical Completion	heights, electrical terminations, electrical tes	
Completion Procedures:		
Substantial Completion	Generally standard; Seeking agreement on c	apacity test and availability test procedures.
	Grid & Power Delivery	
Grid interconnection	NV Energy's (NVE) existing Harry Allen 230 kV	/ substation
	100% with 20 yr. PPA; no economic	
Offtakes and guarantees	curtailment allowed; no other curtailment	100% between two 20 yr. PPAs; no economic curtailment allowed; no other
Badi directs	reimbursement	curtailment reimbursement
-	Based on Leidos study and expectations of ov	
Curtailment	starting at 0.4% in 2017 and ramping to a long	a term value of 1.49% in 2021
	O&M	g-term value or 1.4% in 2021.
Plans	First Solar Electric for first 10 years.	
	Due to lack of planned module washing and li	ittle vegetation shotoward and desire
Costs	decreased JPM base by \$0.5/kW-year. Sponso	or similar to IPM for use 1.5: in
-	term budgets to align with JPM project-adjust	or arrival to strivi for years, see Figure 3
	FSE's O&M contract excludes key items, such	as modulo roniacoment investor 2 to alle
Key considerations	replacement / refurbishment (years 11+) as w	os module replacement. Inverter & tracker
and adjustments	Sponsor model and added to JPM base case.	ren as warrantry expirations not budgeted in
	Environmental / Other	

	Switch Station 1	Switch Station 2
Phase I	Completed; no RECs identified/expected to i	mpact the project. Leidos comments on the
riidse i	Phase I ESA to be addressed.	
Species of concern	See technical discussion below.	
Monitoring	2 years avian monitoring with a potential for	r a 3 rd year.
Special permits or concerns	Due to the Projects being on BLM land additi	ional studies were required. See technical
Special permits or concerns	discussion below.	
	JPM conducted a site visit for Switch 1 alread	dy with favorable findings. A second visit will
Site Visit	be held closer to Switch 2's MCC. We have o	pen questions with respect to Leidos'
JIC VISIC	construction monitoring which we expect to	be addressed prior to our Substantial
	Completion fundings.	

Technical Discussion Items:


- Leidos as IE: This is our first time working with Leidos as solar IE. As has been the case previously, opinions and valueadded commentary are generally insufficient, although Leidos has been working to add these. We will make sure
 opinion is provided in all needed areas prior to funding.
- On-site Period of Record (POR): Leidos relied solely on satellite meteorological sources in the energy estimates. It is
 typically preferred in the solar industry, especially for large projects like Switch 1 & 2 where EPC budgets easily allow
 for a ground measurement campaign, to correlate satellite data to ground data to correct for any potential errors or
 biases in the satellite data. We have accounted for this in our haircut.
- Long-term reference: The Projects' footprint spans 4 adjacent satellite weather tiles. Leidos assumed the long-term irradiance from the NW tile, which was 1.1% higher than the NE tile. We have increased our haircut to account for the selection of the most favorable tile without sufficient support.
- AC Clipping Adjustment: Due to over-build of Project DC capacity to inverter AC capacity, the Project will experience
 clipping losses in the early years of operation (primarily due to inverter limits, but there is also a separate clipping loss
 calculated at the point of interconnection due to AC over-build vs. the PPA limits. These clipping losses will decline over
 time as system degradation occurs. Leidos has estimated this and we have accepted their results and included them in
 our base case.
- Inverters: GE's large LV5 1540 inverters (4 MW each) are a relatively new product line. We are aware of some teething
 issues and retrofits to date with the model used at the Projects and have reduced our year 1 availability assumption.
- Threatened and Endangered Species: Per Leidos, the project may affect, but is not likely to seriously adversely affect
 the Yuma clapper rail, Yellow billed cuckoo, and the Southwestern willow flycatcher. A Desert tortoise relocation area is
 required to be put in place. Additionally, the potential for impacts to these species is further reduced through
 implementation of conservation measures (e.g. leaving areas left in natural a condition as possible) required by BLM for
 protection of wildlife and other resources.
- Environmental Assessment (EA): An EA was required under the National Environmental Policy Act (NEPA) for projects
 that include a major federal action, such as the BLM land crossing. A Determination of NEPA Adequacy, by BLM, was
 issued concluding that the NEPA Documentation fully covers the proposed action and constitutes BLM's compliance
 with NEPA requirements. A Resource Management Plan was approved October 2012.

Technical Stress Case Summaries

Description	Base Case	Combined "P95"	Module Failure	Inverter Failure	Curtailment
Flip (Years)	9.67	10.00	10.33	10.00	10.00
Description	Expected Case	JPM P95 equivalent downside, combines lower resource, higher degradation, and higher O&M	Early module failure, warranty not honored	Early inverter failure, warranty not honored	Over-generation curtailment due to solar buildout, per Leidos
Production adj.	100.0%	91.3% (River Mountains 10- year P95)	Base	Base	92.2%
Availability	98.5%	98.0%	98.5%, with reductions in years 1-5	98.5%, with reductions in years 2-10	Base

Description	Base Case	Combined "P95"	Module Failure	Inverter Failure	Curtailment
Degradation	0.75%	1.25%	Base	Base	Base
O&M Baseline	\$9.5/kW-yr	Base * multiplier	Base	Base	Base
Adder Post-warranty (yrs 6+)	\$2/kW-yr	Base * multiplier	Base	n/a	Base
Adder post module warranty (yrs 11+)	0.5/kW-yr	Base * multiplier	n/a	Base	Base
O&M pattern	escalation only	Multiplier: 150% yr 1-10 200% yr 11-20+	Base + module replacement	Base + inverter replacements	Base
Inverter replacement cost (\$/Wac)	\$0.08/W _{AC} Yr. 10 - 15	Base	Base	\$0.08/W _{AC} Yr. 2 - 10	Base
Module replacement cost (\$W _{DC})	Included	included	\$0.64/W _{DC} 25% replaced Yr. 2-5	included	included

Figure 1. Switch Station 1 & 2 Regional Map







Table 1a and 1b. Switch Station Projects Annual Energy Production and P-Cases

Switch Station 1						Switch Station 2					
Base Output for JPMC		AC				Base Output for JPMC		AC			
Cases with haircut	Year	Clipping	P95	P80	P50	Cases with haircut	Year	Clipping	P95	P80	P50
	1	3.9%	271.0	283.3	296.3		1	0.4%	198.9	208.0	217.5
	2	3.7%	272.3	284.8	297.8		2	0.3%	199.6	208.7	218.3
	3	3.5%	270.9	283.3	296.2		3	0.3%	198.2	207.3	216.8
Degradation: 0.75%	4	3.3%	269.4	281.7	294.6	Degradation: 0.75%	4	0.2%	196.8	205.8	215.3
Haircut: 1.5%	5	3.1%	268.0	280.2	293.0	Haircut: 1.5%	5	0.1%	1 9 5.4	204.4	213.7
Availability YR1: 97.5%	6	2.8%	266.5	278.7	291.4	Availability YR1: 97.5%	6	0.1%	194.0	202.9	212.2
Availability YR2+: 98.5%	7	2.6%	265.0	277.1	289.8	Availability YR2+: 98.5%	7	0.1%	192.6	201.4	210.6
	8	2.4%	263.5	275.5	288.1		8	0.0%	191.1	199.8	209.0
	9	2.2%	262.0	273.9	286.5		9	0.0%	189.6	198.3	207.3
	10	2.0%	260.4	<u>272.3</u>	284.7		10	0.0%	188.1	<u> 196.7</u>	<u> 205.7</u>
	Average		266.9	279.1	291.9		Average		194.4	203.3	212.6
Switch Station 1						Switch Station 2					
Output for Recommended		Curtailme				Output for Recommended		Curtailme			
JPMC Cases - Including		nt				JPMC Cases - Including		nt			
haircut and curtailment	Year	Loss	P95	P80	P50	haircut and curtailment	Year	Loss	P95	P80	P50
	1	0.4%	269.9	282.2	295.1		1	0.4%	198.1	207.1	21 6 .6
Based on Leidos Report	2	0.5%	270.9	283.2	296.2	Based on Leidos Report	2	0.6%	198.3	207.4	216.9
-	3	0.9%	268.5	280.8	293.7		3	1.0%	196.3	205.3	214.7
	4	1.2%	266.2	278.4	291.1		4	1.3%	194.3	203.1	212.4
Note curtailment shown is	5	1.4%	264.2	276.3	288.9	Note curtailment shown is	5	1.4%	192.7	201.5	210.7
based on Operational year	6	1.4%	262.8	274.8	287.4	based on Operational year	6	1.4%	191.3	200.0	209.2
•	7	1.4%	261.3	273.2	285.7		7	1.4%	189.9	198.5	207.6
	8	1.4%	259.8	271.7	284.1		8	1.4%	188.4	197.0	206.0
	9	1.4%	258.3	270.1	282.4		9	1.4%	187.0	195.5	204.4
	10	1.4%	256.7	268.5	280.8		10	1.4%	<u> 185.5</u>	<u>194.0</u>	202.8
	Average		263.9	275.9	288.5		Average		192.2	200.9	210.1



Technical Appendix – Switch Station Projects (Detailed Technical Review)

Discussion applies to both Switch Station 1 and 2 (the "Projects") unless otherwise noted.

Solar Resource Assessment - (by Leidos)

- Net Project Haircut (excluding curtailment/including availability): LT: 1.5%;
- JPM Annual Output Projection (10-yr w/ curtailment and haircut): Switch 1: 288.5 GWh/yr; Switch 2: 210.1 GWh/yr
- JPM Capacity Factor (10-yr): Switch 1: 32.9%; Switch 2: 30.3%
- Campaign and analysis considerations
 - Consultant methods: The assumptions, factors and methods used by Leidos in the solar resource assessment
 are reasonable except where noted below. Supplemental estimates were also performed using First Solar's
 own "PlantPredict" model, yielding results that were not materially different.
 - Onsite period of record: None; while large sites typically have on-site measured data, Leidos relied solely on satellite meteorological sources in the energy estimates. It is typically preferred in the solar industry, especially for large projects like Switch 1 & 2, to correlate satellite data to ground data to correct for any potential errors or biases in the satellite data. We have accounted for this in our haircut.
 - o Long term reference: SolarAnywhere (Clean Power Research, CPR, data is satellite based) v3.2 (1998-2015)
 - o Long term adjustment: Leidos assumed the long-term irradiance from the CPR NW tile which was 1.1% higher than the tile next to it, which also included the project. We have increased our haircut by to account for the selection of the most favorable tile without sufficient support.
 - o Plane-of-array (POA) irradiance: Leidos used an accepted method to derive the POA irradiance—the key "resource" input for solar energy modeling—from the global horizontal irradiance (GHI). The POA irradiance for this site was determined to be significantly higher than the GHI value (142.9% of GHI), with this large boost attributable to the use of a single-axis tracker and the relatively low proportion of diffuse light at this site.
 - o **Terrain and ground cover:** Undeveloped desert with dry stream beds (aka "washes"); site generally slopes from higher elevations in the west to lower elevations in the east. The Projects generally slopes from higher elevations in the west to lower elevations in the east.
 - o Solar regime characteristics: Characterized by Leidos as an arid climate, with hot/dry summers & mild winters.
 - o **Performance test plans:** The Projects will be performing an availability test as well as two capacity tests, a standard "short-term" test as well as a test over the entire first year of operation. We are still working with First Solar to finalize the EPC passing conditions for the availability and short-term capacity test. If we cannot agree on these we may require alternative testing via a third party, such as Leidos.
 - o **Module degradation:** First Solar states 0.5%/year which we did not accept; recommend using 0.75%/year degradation for the JPM booking case as we've done historically.
 - o Inverter considerations: Based on our experience, and discussion with Leidos, we believe a first year availability lower than long-term expectations is appropriate, we have therefore lowered our availability in the first year by 1% to 97.5%. We note Leidos is looking into applying a factor to their own analysis for this and may further influence our recommendation. Additionally we have adopted our standard 98.5% long-term availability starting year 2; Leidos recommended 99%.
 - O AC Clipping Adjustment: Due to over-build of DC capacity to inverter AC capacity, the Projects will experience clipping losses in the early years of operation. The full effects of system degradation will not be seen in overall Project energy generation until the Project no longer experiences any clipping losses. Leidos has estimated this and we have accepted their results and included them in our base case.
- Buildout: There is the potential for an additional 21 MW of solar capacity to be connected at the project POI. We are
 working to ensure appropriate build-out protections (mainly with respect electrical losses) are in place, although
 impacts (if any) are expected to be minor.
- Curtailment: A full discussion is later in this report. Based on the results of the Leidos curtailment analysis and the PPA
 terms we have adopted a long term view of 0.4% initially and ramping to 1.4% in year 5. We will get a bring-down of
 the report, if determined to be needed by Leidos, prior to funding Switch 2.

• Uncertainty: Leidos' forecast 10 yr. uncertainty was 3.7% which we did not accept as it was well below what we have seen projected by other IEs. We have increased the uncertainty to 5.2% to align with what we have seen for projects in similar regimes as forecasted by other IEs.

The net IPM recommended production levels, after adjusting for our haircut, with and without curtailment, are shown in Tables 1a and 1b in the summary section above.

Module Technology

- Modules: Mix of First Solar Series 4 Version 3 (S4v3) modules (types FS-117 & FS120); 1,158,600 total at Switch 1 and 822,240 total at Switch 2; First Solar CdTe (Cadmium Telluride) Series 4 thin film modules have been in production since 2014. Series 4 Version 2 (S4v2) was produced in 2015 and the current S4v3 technology (with mostly minor process changes vs. S4v2, including optimization of materials for improved optical properties and performance) has been in production since 2016.
- Key characteristics: Thin film modules operate on the same physical principles as the more common crystalline silicon panels, but instead of a series of 60 or 72 silicon wafers soldered together into a module, the thin film semiconductor is coated directly onto the glass in a continuous process (a laser then scribes electrically isolated cells into the module). Thin film was developed as a lower cost alternative to silicon. In recent years the cost of silicon has dropped substantially, so that now the cost differential is much more modest. First Solar's CdTe thin film module efficiencies have improved with time, closing the gap vs. the higher efficiencies achieved by crystalline silicon designs, especially after considering that CdTe has better performance at higher temperatures and better ability to make use of indirect light.
- Fleet experience: The First Solar Series 4 series has been manufactured since 2014. Statistics from First Solar indicate total Series 4 volume of 6,256 MW_{DC} through 2016, a first year return rate and cumulative return rates well below 0.025% (250 ppm), but with a breakage rate for Series 4 of 0.08%. These rates are lower than those of previous generations of First Solar's designs but within expectation given the frameless glass-on-glass design, which has higher breakage rates vs. framed crystalline silicon modules.
- JPM experience: We have the close cousin modules, S4v2, at JPM and sPower's Redwood Cluster (~100 MW_{AC} COD in late 2015). Based on discussions with sPower and reported performance to date, the First Solar modules and trackers have been performing well in our portfolio. The first year breakage rate was 0.18%, higher than First Solar's fleet statistics. We are following up to ensure that appropriate spares and are arranged for and that the O&M budget is sufficient.
- Transition to Series 6: First Solar announced in Nov-2016 that it would transition from S4 modules to a new larger form factor product, Series 6 (S6) modules. As a part of this transition, S4 module production lines will be shutdown and new S6 production lines will be installed and qualified. The transition started in Q4 2016 and is expected to be completed in 2018. First Solar plans to continue S4 production and transition its S4 production lines such that it is able to meet all of its obligations in terms of module deliveries and warranty replacements. First Solar has reported that it will build up a stock of S4 modules for warranty replacement purposes, and that it may also keep one S4 production line available for use in the future. We note that this is the same process used when First Solar transitioned from S2 to S3 and as recently as last year converted production lines over to S2 to replenish that warranty stock; this gives added confidence in First Solar's ability to meet warranty needs. We do not see this as presenting any undue risk to the Projects.
- Degradation: First Solar assumes 0.5%/year linear degradation, which Leidos considers reasonable and supportable by the performance of earlier generation modules installed at an NREL test site. Given that system degradation is generally higher than individual module levels, and based on the currently available information and lack of substantiation from First Solar on 0.5%/year, we believe it is appropriate to assume annual degradation of 0.75%/year, as we typically do for other projects, including the sPower 2 Redwood portfolio (First Solar S4v2).
 - We note that modules can become susceptible to a condition known as PID (Potential Induced Degradation) in which their output can degrade under particular sets of voltage and environmental conditions. As the Switch Solar projects use negatively grounded arrays, PID risk is understood to be mitigated.
- Fleet Issues: First Solar enjoys a good reputation in the industry but we are aware of two serial failures that were experienced by First Solar panels in the past. The third item below is a general area of concern with Series 4 modules.
 - Manufacturing tolerance issue (Series 2): From June 2008 to June 2009 a tolerance stacking issue occurred whereby individual tolerances for the multiple manufacturing process steps were set in a way that allowed the end product to be slightly out of tolerance. About 4% of the panels manufactured during that period were affected. Those panels exhibited higher than normal degradation of 10% to 15% the first year. The affected

panels were removed from service under warranty and replaced. First Solar was able to determine that the panels had stabilized after the initial degradation and redeployed them into commercial service at the derated capacity (with transparency to the new end user). First Solar has indicated that the panels are performing well with no further degradation since redeployment.

- Junction box adhesion: Another issue related to a potential risk of junction box adhesion failure on a well-defined population of modules produced in the first half of 2009 with known serial numbers. The root cause of the issue was failure to apply a recommended adhesive primer coating prior to attaching junction box to module. This was later corrected in the manufacturing process. The risk of harm was very limited, with no known incidents of harm or injury. For ground-mounted systems, First Solar repaired or provided replacements for the affected modules under warranty, whether the modules were exhibiting symptoms or not. For rooftop systems First Solar went beyond their warranty obligation and removed and replaced the affected modules at no cost to owner.
- Module breakage: First Solar's Series 4 modules are frameless glass-on-glass modules and are somewhat more prone to breakage vs. typical crystalline silicon modules. As there are no soldered ceil connections (unlike crystalline silicon), CdTe modules may hold up well in temperature cycling and First Solar and Leidos believe these modules will have good durability in this desert location. We have accounted for this in our review of spare parts inventory and O&M costs as well as our stress cases.

Module QA/QC and Testing:

We look for a robust QA/QC program from the module manufacturer and/or sponsor, comparing their proposed efforts against a JPM benchmark approach which includes a suite of studies, tests and inspections (listed below). However in the case of Switch 1 & 2 much of the available quality information came internally via First Solar and was reviewed by Leidos. First Solar arguably has a best-in-class internal quality program, a view held by Leidos as well as other industry participants we have spoken to including third party factory inspector CEA. Based on our review we are comfortable with the quality information which can be provided for Switch 1 & 2, but with a few follow-up requests remaining open as noted below.

- Bankability Study: Leidos. A standalone report was not provided, but very good diligence detail was provided within
 the IE report itself, with details on factory yields, etc. added reflecting resolution of JPM questions on the below topics...
- In-Plant Inspection of Process Sponsor: First Solar has several dozen in-process visual, electrical, and/or mechanical QA/QC steps to promote high reliability modules. These tests range from sample tests to 100% inspection of all modules, depending on the specific operation. A Leidos opinion is pending on this topic and certain portions of the expected reliability data may not yet have been provided by First Solar, but based on broader industry reputation JPM expects it to be acceptable, if not best-in-class, relative to other manufacturers.
- In-Plant Inspection of Panels 3rd party: None. Unlike other large solar transactions, we have not received or required a third party manufacturing audit (e.g. by CEA or SolarBuyer) for First Solar. We believe this is acceptable given that First Solar has one of the most extensive track records in the industry, and has provided internal quality control data to Leidos (discussed further below).
- Qualification Testing of Panel Characteristics (PAN File test): No third party validation-PAN file provided by First Solar, checked by Leidos to match spec sheets. We accounted for lack of third party validation in our haircut.
- Accelerated Life Testing of Bill-of-Materials & Mfg. Process ("HALT test"): First Solar uses an ongoing program to
 monitor product reliability for known or perceived risks to module reliability. Modules are randomly selected on a
 weekly basis from multiple production lines for packaging integrity, interconnects, power performance (i.e., efficiency),
 and cosmetic issues. First Solar uses a combination of short term performance tests and long-term environmental
 exposure tests for a weekly sampling of production modules across all of its production lines.
 - Leidos has received and reviewed reliability and yield data corresponding to 33 weeks of production for Switch
 1, during which 85% of the modules were produced (Q2 2016-Q1 2017). We have requested that Leidos obtain and review the remaining reliability data for Switch 1 and Switch 2.
 - A very small sample of modules each quarter is run through extended cycle testing. The latest results available from VDE, a reputable third party lab, are from Q1 2016 modules and are indicated to be passing, although little detail was provided.
 - We consider the information available to date to be acceptable overall. We will discuss the results with Leidos and First Solar and intend to request updated results as they become available, but this can be a post-close item.

Lab Testing of Production Panels — 3rd Party: None. In light of First Solar's Ongoing Reliability Testing (ORT) program as
described above, which includes weekly sampling across all production lines as well as extended cycle testing on a
limited sample of modules on a quarterly basis, JPM is not requiring third party lab testing of modules directly sampled
from the Switch 1 & 2 projects' inventory.

Racking/Trackers Technology

- Model and key characteristics: First Solar uses a distributed architecture for its tracking systems, with each table of 60 modules actuated by an individual motor, gearbox, and drive screw system. The tracker relies on wind stow to protect the equipment from damage if local wind measurements reach a certain threshold. In these respects (i.e. distributed architecture, wind stow), First Solar's tracker is similar to the popular NEXTracker NX Horizon design, although unlike NEXTracker's recent designs, First Solar's trackers are not self-powered by a mounted solar panel and battery and instead have a wired connection back to the nearest inverter pad.
- Obsolescence: We have recently learned that First Solar has discontinued producing their tracker. Per Leidos, the
 tracker design is very simple, i.e. off-the-shelf components and nothing proprietary, nonetheless we are working to
 understand First Solar's product obsolescence strategy and, if needed, will ensure appropriate protections are in place.
- JPM experience: First Solar trackers are also deployed at sPower 2's Redwood Cluster. Through one year of operation, sPower provided a rough estimate of 99-99.5% tracker availability for Redwood, and indicated that after working through some "teething" issues the performance of these trackers has largely stabilized and has been acceptable.
- IE Opinion: Leidos has indicated that the First Solar tracker design has not changed much over the last year or so, thus potentially making JPM's experience with this tracker at the Redwood Cluster relevant to Switch 1 & 2. Leidos' IE review indicates that the First Solar trackers have undergone accelerated life testing.
- JPM View: Based on Leidos' review and our discussions with sPower we do not believe the First Solar trackers present
 any undue risk to the Projects. The largest uncertainties are with respect to longer-term wear-out risk (mainly motors)
 and maintenance needs. Since existing customers, such as sPower, consider this design to be straightforward and
 serviceable, we believe that our existing major maintenance guidance should cover potential tracker cost needs over
 our investment horizon.

Inverter Technology

- Model background: Switch 1 & 2 use 48 total GE LV5-1540 (4 MVA) inverters supplied by GE. GE Power reported an installed base of 4,500 MW_{AC} of PV inverters worldwide with over 3,100 MW_{AC} of those in the US. First Solar projects alone (not including these projects) are reported to have 1,217 MW_{AC} of GE inverters (323 units) in the fleet. GE is expecting to ship up 800 MW to 1GW of LV5 inverters to US projects in 2017.
 - o GE stopped inverter production at its Pittsburgh plant (which manufactured the 4 MVA inverter model used here) at the end of 2016 and transitioned production to their main power electronics factory in Berlin, Germany. The Pittsburgh plant will now be used for project and supply chain management while centralized spares are located at the facility in Houston, TX.
- Key characteristics: The GE inverters are totally enclosed, with 1P56 rated housing. An air to liquid cooling system is
 used, with the cooling path isolated from the electronics so that no dust is drawn into the electronics circuitry and
 filtering is not required. GE used design-for-reliability processes extensively in developing its inverters and in qualifying
 components used in them, in particular for higher risk areas including power electronics, controls, and cooling. GE has
 stated they have designed their inverters for 25 years but this has not yet been empirically supported.
- JPM experience: NextEra's Indigo Plains portfolio has 34 (136 MVA) of the 4 MVA inverters used at Switch 1 & 2. Performance during initial months appears to have been lower than expected due to teething issues; however we have not been able to confirm this with NextEra. We have accounted for this with a lower first year availability.
- Fleet Issues: Leidos believes that the types of issues observed with the LV5 inverters are comparable to those of other newly introduced utility-scale inverters. Availability data has been requested from GE and First Solar; recent (i.e. February-April 2017) availability for 6 First Solar projects has been good (99.4%) but prior to that availability may have been lower; Leidos and JPM are seeking availability data from COD to current. Per Leidos, GE has a detailed product management process in place to understand the root cause of issues, and address such issues both within its installed base and in its manufacturing and design to prevent future occurrences, which we see as beneficial.
 - o Leidos has reviewed the failures associated with the First Solar fleet and state that the majority of issues observed across the projects were related to hardware issues, including the following: failed components, broken or loose parts, missing parts, wiring errors, coolant leaks, component damage, shipping damage,

- incorrect parts, and hardware design. First Solar's QCR program (detailed in the O&M section) allows easy tracking of all issues within their fleet, including inverters.
- Cooling System: There is currently an open retrofit for the inverters at Switch 2 with regards to the cooling system. We are working to understand this issue further and will ensure proper protections are in place prior to funding, if needed. We note that GE has stated the cooling issue is more to help maintain their one year maintenance schedule and has to date not triggered any high temperature-related inverter derates.
- Availability expectations: Leidos has assumed an availability of 99% which is inline with what GE has stated as their
 expectations. Based on historical issues we have assumed a 98.5% availability, as has been our standard for all inverter
 types to-date.

Warranties

- General: The warranties for the projects are within the range observed in the industry. The major terms of the warranty are summarized below:
- EPC Contract (First Solar Electric):
 - O Defect Warranty commences on the Substantial Completion date and expires 12 months later for all Project Hardware whether provided by EPC contractor, subcontractor or owner. The Defect Warranty period for repaired or replaced items continues for 12 months after the repair or replacement, provided that the entire period is no later than 18 months from Substantial Completion. Note the modules have a separate warranty noted below. This warranty is less than what we generally see and are working to improve it to 24 months but note that we have accepted similar warranties in past transactions.
 - o Design Warranty is 12 months starting at Substantial Completion.
- Module: The module warranties are fairly standard.
 - Performance Warranty: The S4v3 modules have a 25-year power warranty, with the performance guaranteed at 98 percent of the rated power in the first year of operation, followed by 0.5 percent annual degradation in years 2 through 25. Currently the module performance warranty states 0.7%/year while we have been told it is 0.5%/year, we will have this reconciled prior to first funding.
 - Workmanship Warranty: 10 years from substantial completion date of the respective project.
- Availability: Under the O&M agreement with First Solar Electric (FSE) there is an availability warranty where LDs are paid for availability below 99% and a bonus (10-15%) is paid when above or equal to 99%. There are various carve-outs which appear to make it easier for FSE to achieve 99% or greater. We believe our budget accounts for the additional bonus payments but the Sponsor/IE budget does not. We are working to adjust the provisions of the carve-outs in the O&M agreement and/or to adjust the Sponsor model to accurately reflect the bonus.
- Inverter Warranty: The GE inverters come with a 5.5 year warranty from delivery. JPM's booking model reflects expenses for inverter overhauls in years 10-15, and recommended stress cases also cover early inverter failures.
- Trackers/Racking: <u>TBD—no warranty information provided yet</u>. The First Solar O&M contract covers corrective maintenance for the trackers over its 10 year term.
- Main Transformer Warranty: One main transformer per project is used. We are confirming the warranty length.

Engineer, Procure & Construct (EPC) Agreement

EPC contractor

First Solar provides EPC services through its wholly owned subsidiary First Solar Electric (FSE) and have reported completion of 4,000 MW_{AC} of utility scale projects in North America through the end of 2016. In JPM's experience it is unusual that FSE has been constructing Switch 1 & 2 without an executed EPC contract in place. Despite the lack of a formalized contract structure, JPM and Leidos site visits have both indicated that sufficient oversight and QA/QC measures are in place during construction. EPC contracts will be executed prior to funding.

Piles (i.e. steel posts supporting the racking structures)

• The pile designs for the projects were developed using an industry standard approach. Due to the dense caliche soils pre-drilling 100% of the piles was determined to be the most efficient method for this site (to reduce the likelihood of refusal as they are pounded into place, as occurred for a certain percentage of piles at Switch 1). JPM and Leidos observed construction work at Switch 2 and considered it to be in line with good industry practice. Pile construction for Switch 1 was completed prior to JPM / Leidos engagement on these projects; again, Leidos is reviewing the QA/QC records.

Electrical

- Electrical design: The electrical design has been completed and reviewed found by Leidos and found to be acceptable.
- Main Transformer: Both Projects' main 230 kV transformers are provided by Virginia Transformer and are both
 rated for 110 MVA. Switch 2's main transformer has excess capacity which could potentially be used by a later
 expansion phase to use up the remaining 21 MW available under the Project's 200 MW Interconnection
 Agreement. Buildout provisions in the ECCA are currently pending.
- Inverter Step-up Transformers: Each inverter has a padmount transformer supplied by GE Prolec.
- Metering Protocol: Individual meters at each project's main transformer. Loss allocation to be covered in Shared Facilities Agreement.
- Harmonics: First Solar has not confirmed plans to perform harmonics testing at the onset of project operations even thought their 3rd party report required that and filters. We are working to confirm all pre-operational requirements have been met and expect to have language, or comparable protections, requiring the project to perform such testing and all associated costs, including any required filters would not be a project expense.
- Electrical Losses have been calculated during the energy analysis via the PVsyst software package, as is typical.

Completion Procedures

- Mechanical Completion: Requirements for mechanical completion are generally standard, however we are seeking further documentation with regards to confirmation of no grid connection and that all necessary tasks have been completed (e.g. torqueing, pile heights, electrical terminations, electrical testing, etc.).
- Substantial Completion: Requirements for Substantial Completion are generally standard, however First Solar's availability test and capacity test requirements seem relatively easy to meet and we are discussing revising the requirements with First Solar and Leidos.

SCADA

• The project will use a SCADA system in use is one which as been used by First Solar at their other projects. It has the ability to interact with the inverters as well as monitor other typical points such as the meteorological stations, transformers and interconnection disconnect switches. We are still working to confirm the ability of the SCADA system to perform required curtailments or how curtailments will be handled. Generally we don't see the SCADA system as presenting any undue risk to the project assuming curtailments are properly handled.

Interconnection

- The project is located in NV Energy's (NVE) service territory and connects onto lines controlled by NVE.
- The Point of Interconnection (POI), Point of Delivery for the PPA and metering location will be at NV Energy's Harry Allen 230 kV substation.
- Project Transmission line: An approximately 1-mile project constructed and owned 230 kV tie line to the POI.
- Shared Facilities Agreement (SFA): The Projects have entered into a SFA for: (1) the 230 kV bus and associated ancillary equipment in the Project Substation; (2) the Project Transmission Facilities including the 230 kV transmission line to the NVE Harry Allen Substation; and (3) the O&M building, and associated lands and easements that accommodate those facilities.
- **Grid Support capability**: The interconnect agreement requires power factor support and the current design requires the project shared substation have 2 x 22 MVAR capacitor banks. Leidos does not believe this presents any undue risk to the Projects.
- IE opinion: It is Leidos' opinion that the Generator Interconnection Agreement (GIA) is standard in nature and comparable to other GIAs, and the project design will meet the requirements.

Power Purchase Agreement(s)

The key provisions of the three Power Purchase Agreements are the same and discussed together below.

- Nevada Power Company (NPC):
 - o Switch Station 1: 100% of power generated
 - Switch Station 2: 35% of power generated
 - 20 year PPA with an energy price starting at \$38.70/MWh and escalating annually at 3%.
- Sierra Pacific Power Corporation (SPPC):
 - Switch Station 2: 65% of power generated
 - 20 year PPA with an energy price starting at \$38.70/MWh and escalating annually at 3%.

- Guaranteed Output: The Projects are exposed to LDs if production falls below 90% of the adjusted annual supply for any two consecutive years (based on summer (June September) and non-summer months); this amount varies annually as the PPAs account for annual degradation of 0.5%/year. The shortfalls are just above the 1-year JPM P90. An event of default is NOT triggered at any point with respect to the guaranteed output; there are only liquidated damage provisions. We not believe the PPAs present any undue risk to the Projects.
- Liquidated Damages are not capped; during summer months it is the shortfall amount times the greater of 10% of
 the contract price and an amount equal to Average On-Peak Mead Index for the Summer Months minus the
 contract price. For non-summer months the calculation is the same except for the removal of the option to select
 the 10% of contract price if it is greater.
- Curtailment, transmission and other provisions: The Off-Takers are not allowed to curtail the Project for the purpose of receiving economic savings. The Off-Takers are not obligated to compensate the Owners for any energy that is not delivered due to emergency or reliability curtailment. Any curtailed potential net energy will be calculated, documented, and included in the total available for guaranteed performance of the respective Project as used to track potential shortfall. Emergency outages resulting in failure to deliver the potential output of the Facility do not apply to this guaranteed performance calculation.
- Summary: Overall the PPAs do not present undue technical risks.

Curtailment

- Consultant Studies and Conclusions: Leidos conducted a transmission and congestion study which we have accepted. The baseline results indicated modest levels of curtailment starting at 0.4% in 2017 and ramping to 1.4% in 2021. The bulk of the curtailment is over-generation curtailment, described further below. Leidos' downside analysis for 2021, assuming approximately an additional 1,050 MW of Nevada solar build-out, resulted in a large increase in curtailment (7.8%). We have treated the downside as a stress case. We will get a bring-down of the report, if determined to be needed by Leidos, prior to funding Switch 2.
- Over-generation Curtailment occurs when there is more generation than demand and in turn non-dispatchable
 renewable energy is considered marginal and are subject to curtailment. Leidos has indicated such curtailment
 would be emergency or reliability curtailment (as opposed to economic curtailment, which is not allowed under
 the PPAs) even though the curtailment signal could be sent via negative LMPs. Another indicator of overgeneration conditions is when there is little to no basis differential between node and hub and prices are negative,
 i.e. all price points move down together.
- Congestion charges: Since the delivery occurs at the interconnection point, and transmission is the offtakers
 responsibility, no congestion charges are expected with respect to the PPAs.
- Regional considerations and overall recommendation: Given the push for additional renewable energy, being
 heavily driven by state renewable portfolio standards (RPS), we believe that curtailment of solar facilities will
 occur. We have already started to see the impacts of over-generation curtailment on some of our California assets
 given the strong hydro generation this year in California. Based on this we recommend accepting the Leidos results
 and starting curtailment at 0.4% and ramping 1.4%, by 2021 and maintain that for the long-term. If the Leidos
 bring-down shows different results, we will update our view as needed.

Operation & Maintenance

- JPM O&M cost forecast comparison approach: The JPM baseline O&M forecast serves as our primary basis for comparison of sponsor proposed budgets. It is based on discussion with industry O&M providers, full-wrap contracts, industry research and experience with our own portfolio and is the level of O&M budgeting we believe is required to properly operate and maintain a utility-scale solar facility. It is on a dollars-per-kilowatt (DC) per year expenditure basis. The JPM adjusted base for the project is then compared to the Sponsor's pro-forma O&M budget.
- O&M Provider plans: O&M for the first 10 years will be provided by First Solar Electric (FSE). The main expected maintenance activities for the Projects are periodic inspections, preventative maintenance, and corrective maintenance as needed. First Solar does not expect to do module cleaning at this site; the O&M team has confirmed that it monitors other nearby First Solar projects for soiling-related performance loss and that such losses have not justified washing to date. We are still awaiting the plans for maintenance of the transmission line and substation as these are carved out of the FSE contract.

- o First Solar's spare module guidance (years 1-10 of 0.045%/yr and 0.012%/yr thereafter) is below the breakage rate they have reported (0.08%) and what we have seen in our portfolio (0.18% at sPower 2, all replaced under warranty). First Solar's spare parts list has just 150 spare modules, which does not reflect the expected breakage; we are working to determine if additional spares are needed early on to account for breakage likely caused by installation.
- Project specific considerations and adjustments: Given that First Solar does not plan on washing the modules and vegetation abatement costs for this project are expected to be minimal, JPM has lowered its first 10 year baseline guidance by \$0.5/kW-year. Sponsor budget does not account for later year cost impacts, including expiration of the inverter and module warranties and eventual refurbishment or replacement of inverter or trackers.
- The JPM O&M budget recommendation: JPM and Leidos both view First Solar's long-term budget as aggressive.
 Based on economies of scale with these large projects, JPM expects that a budget of \$9.5/kW/year+ escalation
 during the inverter warranty period, \$11.5/kW/year+escalation for years 6-10, and \$12/kW/year thereafter (to
 account for module breakage/ replacement). JPM has also included its baseline guidance for major maintenance in
 years 10-15 (e.g. for inverter and tracker overhauls), consistent with budgeting on prior solar deals and also
 broadly consistent with Leidos' guidance.

Environmental Considerations

The primary environmental review was led by the deal team and counsel. Some observations are noted below.

- Phase I ESA: Environmental Science completed Phase 1 Environmental Site Assessments in February 2017 with no RECs identified at the project. <u>Leidos has raised concerns with respect to the methods and completeness of the ESA, and we expect that it will be updated to address such concerns.</u>
- Environmental Assessment (EA): An EA was required under the National Environmental Policy Act (NEPA) for
 projects that include a major federal action, such as the BLM land crossing. A Determination of NEPA Adequacy, by
 BLM, was issued concluding that the NEPA Documentation fully covers the proposed action and constitutes BLM's
 compliance with NEPA requirements. A Resource Management Plan was approved October 2012.
- Threatened and Endangered Species: Per Leidos, the project may affect, but is not likely to seriously adversely affect the Yuma clapper rail, Yellow billed cuckoo, and the Southwestern willow flycatcher. A Desert tortoise relocation area is required to be put in place. Additionally, the potential for impacts to these species is further reduced through implementation of conservation measures (e.g. leaving areas left in natural a condition as possible) required by BLM for protection of wildlife and other resources.
- Bird and Bat Conservation Strategy (BBCS): Both projects have comprehensive BBCS' with systematic monitoring and adaptive management plans to assist in avoiding, minimizing, and detecting impacts to migratory birds.
- Avian Surveys and planned monitoring (2 yr.) will be implemented for at least two years, with the potential for a third year contingent upon the findings from the first years. The pro forma includes funding for this monitoring over years 1-3 ("mitigation costs").
- There are no landowner or neighbor issues of note. A large amount of water has been needed to manage dust on site roads during construction. Leidos has indicated that there are no long-term needs for dust mitigation.

Site Visit Summary

Ryan Zwilling and Paul Legac visited Switch Stations 1 & 2 on April 18, 2017. Construction progress was observed to be consistent with First Solar's representations, with Switch 1 expected to be ready to begin commissioning their first block upon 1st funding by JPM. Leidos has made a total of three site visits to date in Q2 2017. While it is unusual in JPM experience for construction to take place without an executed EPC contract in place, First Solar has internal processes in place which are resulting in acceptable project quality and JPM and Leidos have not raised any significant concerns to date. We will visit the Projects again around the time of Switch 2 Mechanical Completion. We do have open questions with respect to Leidos' construction monitoring which we expect to be addressed prior to our substantial completion fundings.

APPENDIX A - Econ Summary (page 1 of 2) Switch Station Solar Project 234 MW (DC) ITC MPAPS: 99% / 1% Structure

	JPMCC P50 Bo		JPCCC P95 Seve	en Dozmside	3 P50 Fendin		4 JPMCC P50 U	
	(Accelerated A	inortization)	Selection for the first	ie Downsid	(Sizing C	ase)	(ivo Accelerated	Amortization)
	ger ee			Sept.				
			#1111111111111111111111111111111111111			F		
						6.1		
					2-352			0.000
						and the same while		TO SERVICE
Inputs & Assumptions								
1 Scenario / % of IE P50 (Yr. 1-10 and Yr 11-20) 2 Avg. NCF(AC), 1st yr / 10yrs average	P50 12.90%	96.68% / 94.20% 28.81%	P95 11.80%	85.96% / 78.79% 25.65%	P50 13.30%	100.0% / 100.0% 29.79%	P50 12.90%	96.58% / 94.20% 28.81%
3 Avg. NCF(DC), 1st yr / 10yrs average 4 Nameplate MWs	10.26% 234.3 MW(de)	22.92% 186.3 MW(ac)	9,38% 234,3 MW(dc)	20.40% 186.3 MW(ac)	10.58% 234.3 MW(dc)	23.69% 186.3 MW(ac)	10.26% 234.3 MW(dc)	22.92% 186.3 MW(sc)
5 Prod. Wgt Energy Price (yrs. 1- 10 / yrs. 11 - 20)	\$44.14	\$59.27	\$43.91	\$58.45	\$44.16	\$59.32	234.3 MTT(UC) \$44.14	\$59.27
7 ECCA Date	6/2/2017		6/2/2017		6/2/2017		6/2/2017	
8 1st Funding Date / 2nd Funding Date 9 3rd Funding Date / 4th Funding Date	06/02/17 (\$21.4M) 06/30/17 (\$15.1M)	06/30/17 (\$85.6M) 09/30/17 (\$60.3M)	06/02/17 (\$21.4M) 06/30/17 (\$15.1M)	06/30/17 (\$85.6M) 09/30/17 (\$60.3M)	06/02/17 (\$21.4M) 06/30/17 (\$15.1M)	06/30/17 (\$85.6M) 09/30/17 (\$60.3M)	06/02/17 (\$21.4M) 06/30/17 (\$15.1M)	06/30/17 (\$85,6M) 09/30/17 (\$60,3M)
10 11 Portfolio 30-Year Unlevered IRR	3.50%		-0.33%		5.69%		3,50%	
12 Total Portfolio FMV(DC) 13	\$447,736,879	\$1.91MM / MW	\$447,736,879	\$1.91MM / MW	\$447,736,879	\$1.91MM / MW	\$447,736,879	\$1.91MM / MW
14 ITC Eligible Cost Basis / % of Total Portfolio FMV 15 ITC Amount	\$419,468,622 \$125,840,587	93.69%	\$419,468,622 \$125,840,587	93.69%	\$419,468,622 \$125,840,587	93.69%	\$419,468,622 \$125,840,587	93.69%
16	¥123,940,307	ne addisance man	4120,040,307	W - 4 D - 40 - 11 - 11 - 11 - 11 - 11 - 11 - 11	#123,099,307		4123,04U,36/	
17 Capital Structure 18 Investor Equity	\$182,408,005	% of Portfolio FMV 40.7%	\$182,408,005	% of Portfolio FMV 40.7%	\$182,408,005	% of Portfolio FMV 40.7%	\$182,408,005	% of Portfolio FMV 40.7%
19 JPMCC Equity 20	\$182,408,005	40.7%	\$182,408,005	40.7%	\$182,408,005	40.7%	\$182,408,005	40.7%
21 Sponsor Equity 22	\$265,328,874	59.3%	\$265,328,874	59.3%	\$265,328,874	59.3%	\$265,328,874	59.3%
23 Investor Cash Distributions & Tax Allocations	Cash	Tax	Cash	Tax	Cash	Tax	Cash	Tax
24 Initial Funding Thru 9/30/2017 25 10/31/2017 Thru 12/31/2017	0.00% 30.00%	99.00% 99.00%	0.00% 30.00%	99.00% 99.00%	0.00% 30.00%	99.00% 99.00%	0.00% 30.00%	99.00% 99.00%
26 1/1/2016 Thru 12/31/2022 27 1/1/2023 Thru Target Flip	30.06%	67.00%	37.79%	67.00%	30.00%	67.00%	30.06%	57.00%
27 1/1/2023 1/1/10 1arget Flip 28 Targeted Flip thru Flip	30.50% 31.08%	99.00% 99.00%	42.35% 42.98%	99.00% 99.00%	30.00% NA	99.00% NA	30.50% 31.08%	99.00% 99.00%
29 Post-Flip Thru Year 20' 30 Post Year 20'	9.49%	9.49%	9.49%	9.49%	9.49%	9.49%	9.49%	9.49%
31	5.00%	5.00%	5.00%	5.00%	5.00%	5.00%	5.00%	5.00%
32 Priority % on Sponsor P50 Portfolio Cash 33	27.52%		27.52%		N/A		27.52%	
34 Flip Dates 35 Flip Date	01/31/27	9.67 yrs	05/31/27	40.00	08124105	2.00	24 104 102	4.42
36 Targeted Flip Date	05/31/26	9.00 yrs	05/31/26	10.00 yrs 9.00 yrs	05/31/26 05/31/26	9.00 yrs 9.00 yrs	01/31/27 05/31/26	9.67 yrs 9.00 yrs
37 38 Investor Returns	Generic / JPMCC		Generic / JPMCC		Generic / JPMCC		Generic / JPMCC	
39 Realized Flip Date After-Tax IRR 40 20 Yr, Ali-in After-Tax IRR	7.65% / 8.93% 9.84% / 10.87%		7.65% / 9.02% 8.83% / 9.94%		7.65% / 9.12% 10.57% / 11.57%		7.65% / 8.93% 9.84% / 10.87%	
41								
43 All-in 25 Yr. Pre-Tax & FTC IRR	0.95% 1.54%		-0.90% (0.47%)		1.86% 2.83%		0.95% 1.54%	
44 45 Sponsor Returns								
46 30 Yr. After-Tax IRR 47 30 Yr. After-Tax Cash NPV (8% Discount Rate)	2.40%	-	(1.30%)		4.56%		2.40%	
48	(120,764)		(175,413)		(86,855)		(120,764)	
49 HLBV Accounting 50 HLBV Rate	Flip Date 7.65%	20.0 Yrs.	Flip Date 7.65%	20.0 Yrs.	Flip Date 7.65%	20.0 Yrs.	Flip Date 7.65%	20.0 Yrs.
51 FVO Discount Rate Pre / Post ITC Period 52 Match Funded COF	9.84%	8.32%	9.84%	8.32%	9.84%	8.32%	9.84%	8.32%
53 Basel III ROE	2.43% 21.16%	30.16%	2.43% 17.12%	27.05%	2.43% 27.36%	29.27%	2.43% 25.24%	26.95%
54 Basel III ROA 55 SVA (\$'000)	2.19% \$6,797	3.12% \$13,495	1.77% \$4,055	2.80% \$10,102	2.83%	3.03%	2.61%	2.79%
56 2017 Annual SVA (\$'000)	\$7,675	\$13,483	\$6,167	\$10,102	\$11,144 \$8,886	\$14,690	\$9,666 \$7,675	\$12,241
57 2018 Annual SVA (\$1000) 58 Flip Term Avg SVA (% of Avg RWA)	(\$1,391) 1.14%		(\$1,846) 0.72%		(\$1,146) 1.78%		(\$1,391) 1.56%	
59		4 B-1		44.8.4				
61 2017	Spread Inc. 14,366	Asset Bai. 147,942	Spread Inc. 11,944	Asset Bal. 145,673	Spread Inc. 16,311	Asset Bal. 149,857	Spread Inc. 14,366	Asset Bal. 147,942
62 2018 63 2019	1,269 1,808	120,696 93,554	499 1,698	117,760 90,645	1,730 2,354	122,873 96,117	1,289	120,596 93,975
64 2020	1,610	66,104	1,364	63,056	2,387	69,241	2,226 2,235	67,161
65 2021 66 2022	1,313 1,040	38,178 21,852	1,037 735	34,941 18,361	2,249 2,053	42,025 26,454	2,101 1,910	40,046 24,626
67 2023	1,029	18,299	673	14,427	1,926	23,466	1,791	21,884
69 2025	964 863	14,479 10,348	552 387	10,156 5,496	1,736 1,506	20,072 16,218	1,618 1,406	18,778 15,2 6 1
70 2026 71 2027	738 505	5,873 4,828	199	451 0	1,142	14,499	1,173	11,300
72 Total Thru Yr. 2027	25,525	4,020	1,810 20,900	U	1,027 34,420	13,846	802 30,918	10,637
73 Total Thru Flip 74 Total Thru Flip as % of JPMCC Equity	25,061 13.74%		19,840		32,722 17,94%		30,182 16.55%	
75 76 DROs & Excess Distributions								
77 JPM Max DRO / % of JPM Equity	\$90,544,621	49.64%	\$100,554,247	55.13%	\$88,092,592	48.29%	\$90,544,621	49.64%
78 Year of JPM Max DRO / Year of DRO Reversal 79 JPM DRO at Year 10 / % of JPM Equity	2022 \$38,313,683	2031 21.00%	2022 \$73,333,000	2037 40.20%	2022 \$24,446,216	2029 13.40%	2022 \$38,313,683	2031 21.00%
80 81 ITC								
82 Total Portfolio ITC 83 Actual Investor ITC / % of total	\$125,840,587 \$124,582,181	99,00%	\$125,840,587 \$124,582,181	99.00%	\$125,840,587 \$124,582,181	00.005	\$125,840,587 \$124,582,181	ሰስ ለአው
Post flip percentage through year 20 is set to target a 1.86	\$124,582,181 5% 20-year PT Cash & ITC IRR in		\$124,582,181 el	89.00%	\$124,582,181	99.00%	\$124,582,181	99.00%
- · · · · · · · · · · · · · · · · · · ·		=						

APPENDIX A - Econ Summary (page 2 of 2) Switch Station Soler Project 234 MW (DC) ITC MPAPS: 59% / 1% Structure

	JPMCC P50 Booking RATE in		JPMCC P95 Severe {		JP::iCC P50 Booking i RAT[iii]		JPTICC P95 Severe I TAX RATE	
•						. La Linkarian		
								95/14
				2.0			Valence of	0.00
				in a series				190 340044A
outs & Assumptions								
cenario / % of IE P50 (Yr. 1-10 and Yr 11-20)	P50 12.90%	96.68% / 94.20% 28.81%	P95 11.80%	85.96% / 78.79% 25.65%	P50 12.90%	96.68% / 94.20% 28.81%	P95 11.80%	85.96% / 78.75 25.65
vg. NCF(AC), 1st yr / 10yrs average vg. NCF(DC), 1st yr / 10yrs average	10.26%	22.92%	9.38%	20.40% 186.3 MW(ac)	10.26% 234.3 MW(dc)	22.92% 186.3 MW(ac)	9.38% 234.3 MW(dc)	20.40 186.3 MW(
ameplate MWs rod, Wgt Energy Price (yrs, 1-10 / yrs, 11 - 20)	234.3 MW(do) \$44,14	186.3 MW(ac) \$59.27	234.3 MW(dc) \$43.91	\$58.45	\$44.14	\$59.27	\$43.91	\$58.4
CCA Date	6/2/2017		6/2/2017		6/2/2017		6/2/2017	nome with the c
st Funding Date / 2nd Funding Date rd Funding Date / 4th Funding Date	06/02/17 (\$21.4M) 06/30/17 (\$15.1M)	06/30/17 (\$85.6M) 09/30/17 (\$60.3M)	06/02/17 (\$21.4M) 06/30/17 (\$15.1M)	06/30/17 (\$85.6M) 09/30/17 (\$60.3M)	06/02/17 (\$21.4M) 06/30/17 (\$15.1M)	06/30/17 (\$85.6M) 09/30/17 (\$60.3M)	06/02/17 (\$21.4M) 06/30/17 (\$15.1M)	
ortfolio 30-Year Unlevered IRR	3,44%		-0.60%		3.43%		-0.68%	
otal Portfolio FMV(DC)	\$447,736,879	\$1,91MM / MW	\$447,736,879	\$1.91MM / MW	\$447,736,879	\$1.91MM / MW	\$447,736,879	\$1.91MM / N
C Eligible Cost Basis / % of Total Portfolio FMV	\$419,468,622 \$125,840,587	93.69%	\$419,468,622 \$125,840,587	93.69%	\$419,468,622 \$125,840,587	93.69%	\$419,468,622 \$125,840,587	93.69
FC Amount	\$1/2,840,28/	N -45-24 F 55-1	@123,04U,30/	M of Dodfello EAS	4.20,040,007	% of Portfolio FMV		% of Portfolia F
pital Structure westor Equity	\$182,408,005	% of Portfolio FMV 40.7%	\$182,408,005	% of Portfolio FMV 40.7%	\$182,408,005	40.7%	\$182,408,005	40.7
JPMCC Equity	\$182,408,005	40.7%	\$182,408,005	40.7%	\$182,408,905	40.7%	\$182,408,005	40.
ponsor Equity	\$265,328,874	59.3%	\$265,328,874	59.3%	\$265,328,874	59.3%	\$265,328,874	59.
restor Cash Distributions & Tax Allocations	Cash	Tax	Cash	<u>Tax</u> 99.00%	<u>Cash</u> 0.00%	<u>Tax</u> 99.00%		99.0
idal Funding Thru 9/30/2017 0/31/2017 Thru 12/31/2017	0.00% 30.00%	99.00% 99.00%	0.00% 30.00%	99.00%	30.00%	99.00%	30.00%	99.
/1/2018 Thru 12/31/2022	38.63%	67.00%	50.07%	67.00%	41.16%	67.00%		
/1/2023 Thru Target Flip	40.26%	99.00% 99.00%	56.11% 59.72%	99.00% 99.00%	42.84% 43.52%	99.00% 99.00%		
argeted Flip thru Flip Post-Flip Thru Year 20'	40.77% 10.03%	10.03%	10.03%	10.03%	9.79%	9,79%	9.79%	9.1
Post Year 20	5.00%	5.00%	5.00%	5.00%	5.00%	5.00%	5.00%	5.0
riority % on Sponsor P50 Portfolio Cash	36.47%		36.47%		38.80%		36.80%	
ip Dates		40.00	05/31/27	10.00 yrs	05/31/27	10.00 yrs	05/31/27	10.00
in Data argeted Flip Date	0 5/31/27 05/31/26	10.00 yrs 9.00 yrs	05/31/26	9.00 yrs	05/31/26	9.00 yrs		
vestor Returns	Generic / JPMCC		Generic / JPMCC	_	Generic / JPMCC		Generic / JPMCC	
Realized Flip Date After-Tax IRR 20 Yr. All-in After-Tax IRR	7.65% / 8.76% 9.80% / 10.59%	,	7.65% / 8.79% 8.91% / 9.77%		7.65% / 8.70% 9.76% / 10.50%		7,65% / 8,72% 8,90% / 9,70%	
All-in 20 Yr. Pre-Tax & ITC IRR	3.73%		2.28%		4.34%		3.00%	
All-in 25 Yr. Pre-Tax & ITC IRR	4.10%		2.52%		4.68%		3.21%	
oonsor Returns	2.49%		(1.66%)		2.53%		0.00%	
80 Yr. After-Tax IRR 80 Yr. After-Tax Cash NPV (8% Discount Rate)	(125,085)		(184,073)		(125,988)		(186,189)	
LBV Accounting	Fip Date	20.0 Yrs.	Filip Date	20.0 Yrs.	Flip Date	20.0 Yrs.	Flip Date	20.0
ILBV Rate	7.65%		7.65%		7.65%		7.65%	
FVO Discount Rate Pre / Post ITC Period	9.80% 2.43%	8.32%	9.80% 2.43%	8.32%	9.76% 2.43%	8.32%	9.76% 2.43%	
Match Funded COF Basel III ROE	24.08%	33.85%	19,41%	30.74%	24.69%		20.00%	31.6
Basel III ROA	2.49%		2.01% \$5,958	3.18% \$13,603	2.55% \$10,200	3.65% \$18,945	2.07% \$6,479	
SVA (\$'000) 2017 Annual SVA (\$'000)	\$9,572 \$7,662	\$17,717	\$5,951	\$15,000	\$7,641	\$10,010	\$5,858	
2018 Annual SVA (\$'000)	(\$279) 1.44%	ı	(\$842) 0.96%		\$95 1.50%		(\$479) 1.02%)
Filip Term Avg SVA (% of Avg RWA)				A Bel		Accet Bui		Asset
(\$°000) 2017	Spread Inc. 14,345	Asset Bal. 147,920	Spread Inc. 11,597	Asset Bal. 145,324	Spread Inc. 14,312	Asset Bal. 147,887	11,447	145
2018	2,747	131,191 103,577	1,958 2,119	129,226 100,414	3,116 2,354	133,850 106,021	2,359 2,187	
2019 2020	2,275 1,993	75,501	1,746	72,034	2,045	77,705	1,803	74
2021	1,660	46,827	1.373 1,010	43,005 25,394	1,700 1,361	48,764 31,252		
2022 2023	1,339 1,275	29,620 24,972	885	20,272	1,281	26,259	900	21
2024	1,134	19,687	682 427	14,642 8,435	1,118 908	20,782 14,755		
2025 2026	947 727	14,305 8,178	140	1,605	661	8,127	86	. 1
2027	474	5,570	1,459 23,396	(0)	418 29,276	- 5,339	1,568 23,883	
Total Thru Yr. 2027 Total Thru Flip	28,916 28,632	=	22,539	-	29,024	_	22,962	Ξ.
Total Thru Flip as % of JPMCC Equity	15.70%	<u>-</u>	12.36%	_	15.91%	<u>-</u>	12.59%	<u>•</u>
ROs & Excess Distributions		10.000	\$400 BE4 #70	EE 480/	\$90,658,510	49.70%	\$100,676,994	55.
JPM Max DRO /% of JPM Equity Year of JPM Max DRO / Year of DRO Reversal	\$90,632,361 2022	49.69% 2031	\$100,651,578 2022	55.16% 2038	\$90,658,510 2022	2032	2022	2
JPM DRO at Year 10 / % of JPM Equity	\$46,617,419		\$81,009,468	44.41%	\$48,527,548	26.60%	\$82,918,814	45.
rc					Pane pan Fo	,	\$125,840,58	7
	\$125,840,58		\$125,840,587		\$125,840,587			
Total Portfolio ITC Actual Investor ITC: / % of total	\$124,582,18	1 99.00%	\$124,582,181	99.00%	\$124,582,181	1 99.00%	10 JULY 10 10 10 10 10 10 10 10 10 10 10 10 10	

APPENDIX B - PIOC Return on Capital Template Switch Station Solar Project 234 MW (DC) PIOC Return on Capital Template

TOI Energy - Switch Station Solar Project 234 MW (DC)	Solar Project 234	MW (DC)							
Asset	Switch Station 5	Solar Project 234	MW (DC) with	Switch Station Solar Project 234 MW (DC) with projects located in Clark County, Nevada	n Clark Count	iy, Nevada			
Investment Structure	Partnership flip	structure, targeti	ng a 9.67 year	Partnership flip structure, targeting a 9.67 year Flip with a 7.65% IRR after-tax (generic 35% tax rate)	IRR after-tax	(generic 35% ta	ax rate)		
TOI Energy Investment	\$182,408,005 e	xpected to be fur	//08/60 kg papu	\$182,408,005 expected to be funded by 09/30/2017 over a period of six months	d of six month	જુ			
JPMCC 20yr all-in IRR	9.84%	after-tax	15.64% p	pretax equivalent					
Flip Constraint	Under P95 Sever at yr 10 years, wi	e Downside Cas th an 8.83% % a	e (including lov II-in AT IRR (35	Under P95 Severe Downside Case (including lower production, higher degradation and lower availability), flip rate is achieved at yr 10 years, with an 8.83% % all-in AT IRR (35% generic tax rate)	gher degradat :e)	ion and lower a	vailability), flip ra	ate is achieved	
Average Basel III ROA thru flip Average Basel III ROA all-in	2.19% 3.12%								
Average Basel III ROE thru flip Average Basel III ROE all-in	21.16% 30.16%								
	Cash					Cumulative	Annual	Year-End	
Annual Estimates (\$'000)	Distributions	입	Revenue	Earnings	SVA	Basel III ROE	Basel III ROA	Book Balance	
2017	848	124,582	14,366	8,675	7,675	87.3%	7.8%	147,942	
2018	4,527	•	1,289	104	(1,391)	35.4%	%L.O	120,696	
2020	4,536 4,600		1.610	589 589	(310)	21.8%	%8°0	93,334 66.104	
2021	4,735		1,313	547	(42)	20.5%	1.0%	38,178	
2022	4,812	1	1,040	493	156	20.1%	1.5%	21,852	
2023	4,893	1	1,029	541	318	20.2%	2.2%	18,299	
2024	5,039		964	519	335	20.5%	2.4%	14,479	
2025	5,188	•	863	476	336	20.8%	2.7%	10,348	
2026	5,342	•	738	420	327	21.1%	3.4%	5,873	
2027	1,633	ı	505	583	 30	21.4%	3.4%	4,828	
Total	46,153	124,582	25,525	13,225	7,009				

APPENDIX C - JPMCC P50 Pro Forma Summary

Switch Station Solar Project 234 MW (DC) (\$000s)

Portfolio Economics	107																					
Installed Capacity (MW)	186.3 28.81%																					
Power Generation (MWh)	210,587	612,604	511,840	507,072	602,273	498,179	495,025	491,825 4	488,582 4	485,298 4	481,975 4	478,617 4	475,226 4	471,805 4	468,361 4	464,894 4	461,406 4	457,891 4	454,345 4	450,763 4	447,181	9,815,658
Blended Power Price (\$AMWh)	35.89	39.16	40.33	41.54	42.79	44.07	45.40	46.76	48.18	49.61	51.09	52.63	54.21	55.83	57.51	59,23	61.01	62.84	64.73	66.67	61.57	
Power Revenue	7,559	20,069	20,644	21,065	21 492	21,956	22,472	22,996	23,530	24.073	24,626	25,188	25,780	26,342	26,934	27,537	28,150	28,774	29,408	30,051	27,533	506,157
Operating Expenses	(1,508)	(8,320)	(5,535)	(5,721)	(5,713)	(5,998)	(6,350)	(6,417)	(6,487)	(6,867)	(8,063)	_				_	_		(7,526)	(7,634)	(7,463)	(155,07
Tax Depreciation Taxable Income	(38,432)	(128,498) (113,747)	(62,766)	(32,087)	(41,713)	(13,972)	(1,613) 14,509	(1.613) 14,967	(1,613) 15,430	15,494	(1,613) 14,950	(1,613) 13,926	(1,613)	(1,613)	(1,636)	(1,152) 1 6,780	20,685	21,208	21,738	22,273	19,973	(33,105)
Total Distributable Cash (Incl. 1-Mth Lag) Total ITC	5,367 125,841	15,091	15,108	16,317	15,758	15,878	16,098	16,556	17,019	17,160	16,633	16,681	14,484	14,586	15,634	17,566	20,804	21,327	21,856	22,391	20,522	350,936 125,841
Partnership Allocations	2017	2018	2019	2020	2021	2022.	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	Total
Sponsor Cash (excl RECs) Investor Cash (excl RECs)	4,519 848	10,563	10,572	10,718	11,023 4,735	11,166	11,205 4,893	11,516 5,039	11,831 5,188	11,818 5,342	15,000	14,193	13,109	13,202	14,150 1,484	15,899 1,867	18,829	19,302 2,024	19,781 2,075	20,266	1,350	287,834 63,102
Sponsor Net Taxable Income Investor Net Taxable Income	(364)	(37,537)	(20,778)	(10,886)	(9,131) 4,735	(5,486)	(882) 4,893	(878) 5,039	(873) 5,188	(872)	(878) 1,633	(888)	(899) 1,375	(896) 1,385	8,129 1,646	14,041	17,629	18,171 2,024	18,873 2,075	19,668 2,125	18,403	23,688 (56,793)
Sponsor ITC Used Investor ITC Used	124,582					1 1									• 1				1 1	1,258		1,258 124,582
JPMCC Total Investment	182,408 100,00% 37,54%																					
Project Cash % Allocations Project Tax and ITC % Allocations	15,80% 99,00%	30.00%	30.02%	30.03% 67.00%	30.05% 67.00%	30.12% 67.00%	30.39% 99.00%	30.44% 99.00%	30.48% 99.00%	31.13% 99.00%	9.82% 13.04%	9.49% 9.49%	9.49%	9.49% 9.49%	9.49% 9.49%	9.49% 9.49%	9.49% 9.49%	9.49% 9.49%	9.48% 9.48%	9.49% 9.49%	6.58% 7.11%	
Cash Distributed from LLC (incl RECs) ITC Tax Benefis (Liabilities) Total ATGF to JPMCC	848 124,582 12,624 136,064	4,527 26,674 31,201	4,536 (725) 3,810	4,600 (1,610) 2,990	4,735 (1,657) 3,078	4,812 (1,684) 3,128	4,893 (1,713) 3,180	5,039 (1,764) 3,276	5,188 (1,816) 3,372	5,342 (1,870) 3,472	1,633 1,061	1,469 (521)	1,375 (481) 894	1,385 (485) 900	1,484 (576) 908	1,867 (584) 1,084	1,975 (891) 1,284	2,024 (709) 1,316	2,075	2,125	1,350 (493) 857	63,102 124,582 19,878 207,562
JPINCC Book liteome	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	Total
Year-End Book Value	147,942	120,696	93,554	68,104	38,178	21,852	18,299	14,479	10,348	5,873	4,828	3,897	3,341	2,751	8,314	7,388	6,084	4,632	3,005	1,186		
Asset Amorézation Cash Distributions Pre-Tax Book Income	(34,486) 848 (33,618)	(27,248) 4,527 (22,719)	(27,142) 4,538 (22,606)	(27,450) 4,600 (22,850)	(27,926) 4,735 (23,191)	(16,326) 4,812 (11,513)	(3,553) 4,893 1,340	(3,820) 5,039 1,220	(4,131) 5,188 1,067	(4,475) 5,342 867	(1,046) 1,633 587	(830) 1,489 658	(656) 1,375 719	(590) 1,385 794	5,563 1,484 7,047	(928) 1,867 741	(1,304) 1,975 671	(1,452) 2,024 573	(1,628) 2,075	(1,840) 2,125 286	(1,186) 1,350 184	63 102 63,102
After-Tax Book Income 1 Book-Tax Depreciation Diff Benefit Net After-Tax Income	(21,148) 23,108 1,957	(14,292)	(14,221)	(14,374)	(14,589)	(7,243)	843	787	965	545	369	£ .	452 . 25	500	4,433	466	422	360	282	180	116	(75,052) 23,106 (51,946)
Pre-Tax Equivalent 2 ITC Deferred Income	3,112	(22,719)	(22,606)	(22,850)	(23,191)	(11,513)	1,340	1,220	1,057	. 967	587	658	719	794	7,047	741	671	573	448	286	48 · ·	(82,578) 124,582
COF Breeze Breeze Inches	(700)	(908)		(458)	(413)	1,040	(311)	(258)	(194)	(128)	(8) (8)	88	(56) 662	746	(87)	(124)	(108) 564	(82)	29.	32 38 38	<u></u>	36,95
acc opress income	*	800	000	000	0.00				} ·													
Englisher:	"Alles Ton Book Income" well con the "One Toy Book Income" by the 18 men																					

APPENDIX C - JPMCC P95 Pro Forma Summary

Switch Station Solar Project 234 MW (DC) (\$000's)

Portrollo aconomics Installed Capacity (MW).	186.3	2018	2613	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	Tatal
Net Capacity Factor (10 yrs)	25.65%	466,642	462,197	465,515	448,813	442,746	437,512	432,231	426,907	421,539	416,132	410,689 4	405,212	399,704	394,171 3	388,613 3	383,034 3	377,426 3	371,790	366,119	360,444	8,459,920
Blended Power Price (\$MWM)	35.89	39.16	40.17	41.54	42.47	44.07	44.90	48.76	47.49	48,61	50.22	52.83	53.09	55.83	56.11	59.23	59.28	62.84	62.61	66.67	61.01	
Power Revenue	6,912	18,269	18,568	18,923	19,062	19,513	19,644	20,210	20,274	20,910	20,888	21,613	21,513	22,316	22,117	23,018	22,707	23,717	23,280	24,408	21,991	429,865
Operating Expenses Tax Depreciation Taxable Income	(2,124) (42,383) (37,896)	(8,554) (128,486) (118,781)	(6,792) (77,873) (66,097)	(6,985) (47,431) (35,502)	(6,989) (41,713) (29,641)	(7,424) (29,930) (17,841)	(7,958) (1,613) 10,073	(8,085) (1,813) 10,532	(8,176) (1,613) 10,486	(8,698) (1,613) 10,600	(10,340) (1,613) 8,946	(13,437) (1,613) 6,564	(15,224) (1,813) 4,676	(15,833) (1,613) 5,070	(15,380) ((1,636) 5,120	(1,152) (8,084	(11,602) ((144) 10,962	(11,808) (144) 11,784	(12,022) (144) 11,114	(12,242) (144) 12,022	(11,612) (97) 10,282	(212,828) (384,190) (167,163)
Total Distributable Cash (incl. 1-Mth Lag) Total ITC	4,382	12,069	11,823	11,868	12,140	12,062	11,796	12,009	12,249	12,116	11,011	8,129	699'9	6,307	7,076	8,576	11,480	11,526	11,704	11,714	10,706	217,412 125,841
Partnership Altocations	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	Total
Sponsor Cash (excl RECs) Investor Cash (excl RECs)	3,707 675	7,720	7,480	7,421 4,447	7,540	7,351	6,934 4,863	6,992 5,018	7,076 5,172	6,821 5,295	8,751 2,259	7,358	6,036	5,709 599	6,403 672	7,762	10,390	10,432	10,593	10,602	10,024	163,102 54,310
Sponsor Net Taxable Income Investor Net Taxable Income	(376) (37,219)	(38,538) (77,873)	(21,850) 4,343	(12,132) 4,447	(10,484) 4,600	(6,885) 4,711	(1,046) 4,863	(1,041) 5,018	(1,042) 5,172	(1,040) 5,295	(1,057) 2,259	(1,081)	(1,100)	(1,096) 599	(1,095) 672	(1,065)	(1,037) 1,090	(891) 1,094	(619) 1,111	(324)	2,370 863	(101,527) (85,626)
Sponsor ITC Used investor ITC Used	124,582	· 1		• •			1 1		1.1		, ,							, .				124,582
JPMCC After-Tax Cash Flow	2017	2018	2019	2020	. 1202	2022	2023	2024	- 2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	Fotal
JPMCC Total Investment. JPMCC Share JPMCC Tax Rate	182,408 100,00% 37,54%																					:
Project Cash % Altocations Project Tax and ITC % Allocations	15.41% 99.00%	36.04% 87.00%	36.73% 67.00%	37,47% 67.00%	37.88% 67.00%	39.05% 67.00%	41.22% 99.00%	41.78% 99.00%	42.23% 99.00%	43.70%	20.52% 52.80%	9.49% 9.49%	9.40% 9.49%	9.49%	9.49%	9.49% 9.49%	9.49% 9.49%	9.49% 9.49%	9.49% 9.49%	9.49%	6.37%	
Cash Distributed from LLC (incl RECs) To a Benefits (Liabilities) Total ATCF to JPMCC	675 124,582 13,027 138,284	4,349	4,343 (1,520) 2,823	(1,556)	4,600 (1,610) 2,990	4,711 (1,649) 3,062	4,863	5,018	5,172	5,285	2,258	772 (270) 502	633 	598 240 388	672 (235)	814 (285) 529	1,090 (381) 708	1,094 (383) 711	1,111 (389) 722	1,112	(302) 380	54,310 124,582 22,969 201,881
JPMCC Book Income	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	foraf
Year-End Book Value	145,673	117,760	90,645	63,056	34,941	18,361	14,427	10,156	5,486	451				1		1	,			•	•	·
Assel Amortization Cash Distributions Pre-Tax Book Income	(36,735) 675 (36,080)	(27,914) 4,349 (23,564)	(27,114) 4,343 (22,772)	(27,589) 4,447 (23,142)	(28,115) 4,800 (23,516)	(16,580) 4,711 (11,870)	(3,934) 4,863 929	(4,271) 5,018 746	(4,660) 5,172 512	(5,045) 5,285 250	(451) 2,259 1,808	277	633	599	672	814 814	1,090	1,094	1,11	1,112	682	54,310
After-Tax Book income 1 Book-Tax Depreciation Driff Benefit Net After-Tax Income	(22,684) 23,106 422	(14,624)	(14,326)	(14,558)	(14,792)	(7,467)	584	470	322	157	1,137	485	398	377	4 22	512	686	688	689	7007	429	(80,583) 23,106 (67,477)
Pre-Tax Equivalent 2 ITC Deferred Income COF	670 11,955 (681)	(23,584) 24,916 (853)	(22,772) 24,916 (446)	(23,142) 24,916 (411)	(23,515) 24,916 (385)	(11,870) 12,862 (358)	926	746	512	250	1,808	772	633	288	672	11	1,090	1,094	11. 11.	1,112	682	(91,368) 124,582 (3,750)
JPMCC Spread Income	11,944	667	1,698	1,364	1,037	182	673	552	387	189	1,810	E	632	2897	0/9	912	1,088	1,092	94,	1,110	188	29,463
Footnates: 1	"After-Tax Book income" reduces the "Pre-Tax Book income" by the IB management repor The "Pre-Tax Equivalent" calculation is a gross up of the "Net After-Tax income" total it.e.	ok income" i Equivalent"	educes the calculation is	Pre-Tex Bod a gross up o	k Income" by X fhe "Net At	the IB mani ter-Tax inco	agement rep. me*total (i.e.	reporting rate of 37.093% (f.e. divided by 62.097%)	37.093%													

E. Technical Review

FINAL INVESTMENT COMMITTEE

J.P.Morgan